



**City of Phoenix
Office of the City Engineer
Design and Construction Procurement**

**PW16810007
STATE ROUTE 85 LANDFILL MONITORING WELL**

ADDENDUM NO. 2

ISSUE DATE: March 18, 2024

Bidders are hereby notified that the Bidding and Contract Documents for the above project, for which Bids are to be received on March 26, 2024, are amended as follows:

- 1Q. The City issued Addenda No. 1 on March 14, 2024, for the State Route 85 Landfill Monitoring Well. The Addenda specifies a Grundfos 5SQ07-230 Pump to be set at 400 feet below ground surface. Also included in the Addenda is a Figure 2 Well Diagram for MW-6R that depicts a static water level of 440 feet. Please note that the setting depth of the pump must be at a greater depth than the static water level for the pump to function. Please clarify the pump setting depth.
- 1A. The pump spec in the addendum shows the details for the **existing** pump in MW-6, so that the phase and wiring style can be matched as requested during the field visit. We are requesting a new pump for the new well MW-6R. The requested placement of the new pump is specified in Section 7.7 Pump Installation, 600 feet bgs capable of pumping 10 gpm.

NOTE: Bidders must acknowledge receipt of this Addendum by listing the number and date, where provided, on the PROPOSAL P-1.

END OF ADDENDUM

A circular professional engineer seal for Barbara Sylvester, Registered Professional Engineer, License No. 40268, State of Arizona. The seal includes the text "Registered Professional Engineer, License No. 40268, BARBARA SYLVESTER, State of Arizona" and "Date Signed 3/18/2024". Below the seal is a handwritten signature in blue ink.