



**City of Phoenix
Office of the City Engineer
Design and Construction Procurement**

**WS85509031 (WIFA)
WATER MAIN REPLACEMENT ABB: MOUNTAIN VIEW ROAD TO PEORIA AVENUE
AND 19TH AVENUE TO 15TH AVENUE**

ADDENDUM NO. 2

ISSUE DATE: March 13, 2025

1. Bidders are hereby notified that the Bidding and Contract Documents for the above project, for which Bids are to be received on March 18, 2025, are amended as follows:

Please delete the following: **Bids Will Be Due: Tuesday, March 18, 2025, at 2:00 P.M.** and replace with the following:

**BIDS WILL BE DUE: TUESDAY, MARCH 25, 2025, AT 2:00 P.M.
SUBMITTED INTO THE DESIGN AND CONSTRUCTION PROCUREMENT BID BOX LOCATED ON
THE 1ST FLOOR LOBBY OF THE PHOENIX CITY HALL BUILDING, 200 W. WASHINGTON STREET,
PHOENIX, ARIZONA, 85003**

**BIDS WILL BE READ: TUESDAY, MARCH 25, 2025, AT 2:00 P.M.
ON 5TH FLOOR, ROOM 5 WEST
PHOENIX CITY HALL
200 W. WASHINGTON STREET
PHOENIX, AZ 85003-1611**

***All times are local Phoenix time**

2. Bid Tab P-2 to 3 is hereby deleted in its entirety and replaced with the following: See attachment.
3. See Attachment A with questions and answers.



NOTE: Bidders must acknowledge receipt of this Addendum by listing the number and date, where provided, on the PROPOSAL P-1.

END OF ADDENDUM

Item No.	Description	Unit	Quantity	Unit Price	Total Cost
1 E6992000	ALLOWANCE FOR STORM WATER POLLUTION PREVENTION BEST MANAGEMENT PRACTICES (BMP'S)	Job	1	\$25,000.00	\$25,000.00
2 M1000000	MATERIALS TESTING & QUALITY CONTROL	Job	1		
3 M1002005	MOBILIZATION / DEMOBILIZATION	Job	1		
4 M1042005	ALLOWANCE FOR EXTRA WORK	Job	1	\$250,000.00	\$250,000.00
5 M1058000	CONSTRUCTION SURVEYING AND LAYOUT	Job	1		
6 M3362000	SLURRY SEAL COAT	Sq. Yd.	57,550		
7 M3362100	MICRO SEAL	Sq. Yd.	28,210		
8 M3369794	ASPHALT CONCRETE FOR PERMANENT PAVEMENT REPLACEMENT, 4" THICK PER SPECIAL PROVISIONS (RESIDENTIAL STREET)	Sq. Yd.	4,480		
9 M3369795	ASPHALT CONCRETE FOR PERMANENT PAVEMENT REPLACEMENT, 6" THICK PER SPECIAL PROVISIONS (COLLECTOR STREET)	Sq. Yd.	2,600		
10 M3369798	ASPHALT CONCRETE FOR PERMANENT PAVEMENT REPLACEMENT, 8" THICK PER SPECIAL PROVISIONS (ARTERIAL STREET)	Sq. Yd.	820		
11 M3370100	CRACK SEAL	Sq. Yd.	85,760		
12 M4012000	TRAFFIC CONTROL DEVICES	Job	1		
13 M4013000	ALLOWANCE FOR UNIFORMED, OFF-DUTY LAW ENFORCEMENT OFFICER	Job	1	\$50,000.00	\$50,000.00
14 M6000006	6"X2" TAPPED CAP WITH 2" I.P. CORP.	EA	5		
15 M6101801	NEW WATER METER BOX AND COVER FURNISH & INSTALL AT NEW LOCATION	EA	70		
16 M6101802	NEW WATER METER BOX AND COVER, FURNISH & INSTALL AT EXISTING LOCATION.	EA	448		
17 M6101805	WATER SERVICE CONNECTION (MAIN TO METER)	EA	518		
18 M6101810	3/4" OR 1" WATER METER SERVICE CONNECT PIPE AND FITTINGS, MAIN TO METER, FURNISH & INSTALL	L.F.	12,979		
19 M6101815	1-1/2" OR 2" WATER METER SERVICE CONNECT PIPE AND FITTINGS, MAIN TO METER, FURNISH & INSTALL	L.F.	156		
20 M6102006	6" DUCTILE IRON WATER PIPE AND FITTINGS, FURNISH & INSTALL	L.F.	10,582		
21 M6102008	8" DUCTILE IRON WATER PIPE AND FITTINGS, FURNISH & INSTALL	L.F.	2,759		
22 M6102012	12" DUCTILE IRON WATER PIPE AND FITTINGS, FURNISH & INSTALL	L.F.	3,180		
23 M6104004	4" DUCTILE IRON WATER PIPE AND FITTINGS, RESTRAINED, FURNISH & INSTALL	L.F.	27		
24 M6104006	6" DUCTILE IRON WATER PIPE AND FITTINGS, RESTRAINED, FURNISH & INSTALL	L.F.	9,661		
25 M6104008	8" DUCTILE IRON WATER PIPE AND FITTINGS, RESTRAINED, FURNISH & INSTALL	L.F.	1,119		
26 M6104012	12" DUCTILE IRON WATER PIPE AND FITTINGS, RESTRAINED, FURNISH & INSTALL	L.F.	2,383		
27 M6104301	WATERLINE CUT AND PLUG PER DET. P-1343, UP TO & INCL. 12"	EA	25		
28 M6104400	WATERLINE CUT AND PLUG PER DET. P-1344, UP TO & INCL. 12"	EA	4		

29 M6106002	REMOVE EXISTING VALVE BOX, AND COVER, RESTORE SURFACE	EA	142		
30 M6108006	FIRE HYDRANT FURNISH & INSTALL	EA	59		
31 M6108007	FIRE HYDRANT, SALVAGE & DELIVER TO THE CITY OF PHOENIX	EA	29		
32 M6153000	CONSTRUCT WATER OR SANITARY SEWER ENCASEMENT, MAG. STD. DET. 404	L.F.	1460		
33 M6303006	4" VALVE, BOX, AND COVER, FURNISH & INSTALL	EA	1		
34 M6303006	6" VALVE, BOX, AND COVER, FURNISH & INSTALL	EA	68		
35 M6303008	8" VALVE, BOX, AND COVER, FURNISH & INSTALL	EA	8		
36 M6303012	12" VALVE, BOX, AND COVER, FURNISH & INSTALL	EA	10		
37 M6303106	6" VALVE, FLG. X MJ. BOX AND COVER, FURNISH & INSTALL	EA	58		
38 M6304010	8" X 6" TAPPING SLEEVE AND VALVE, BOX, & COVER, FURNISH & INSTALL	EA	4		
39 M6304025	8" X 8" TAPPING SLEEVE AND VALVE, BOX, & COVER, FURNISH & INSTALL	EA	1		
40 M6304055	12"X6" TAPPING SLEEVE AND VALVE, BOX, & COVER, FURNISH & INSTALL	EA	5		
41 M6304060	12"X8" TAPPING SLEEVE AND VALVE, BOX, & COVER, FURNISH & INSTALL	EA	1		
42 M6304070	12"X12" TAPPING SLEEVE AND VALVE, BOX, & COVER, FURNISH & INSTALL	EA	2		
43 M6309065	DEBRIS CAP, INCLUDING LOCATOR COIL, FURNISH AND INSTALL	EA	157		
44 M6309066	DEBRIS CAP, INCLUDING LOCATOR COIL, NON-PAVED AREAS, FURNISH AND INSTALL	EA	1		
45 M6012100	REMOVE AND DISPOSE EXISTING 6" TRANSITE WATERLINE RESTORE SURFACE	LF	520		
46 M6103706	WATERLINE REALIGNMENT, 6" AND 8" CONTINGENT ITEM	EA	10		
47 M6103710	WATERLINE REALIGNMENT, 10" AND 12" CONTINGENT ITEM	EA	5		
48 M6153000	CONSTRUCT WATER OR SANITARY SEWER ENCASEMENT, MAG. STD. DET. 404 CONTINGENT ITEM	L.F.	500		
49 M6101801	RELOCATE EXISTING METER TO NEW LOCATION (PER THE CONTINGENT ITEM	EA	20		
BASE BID (ITEMS 1 THROUGH 49 - INCLUSIVE			\$		
_____ & ____/100 DOLLARS					
WRITTEN WORDS					

Prepared By:

Signature

Name

Position/Title

Firm Name

Attachment A

Addendum 2

March 13, 2025

Information to Bidders – The following is provided to Bidders for information only (Refer to Specifications, and Drawings for construction instructions):

Question 1: Will there be an Addendum that addresses the pay item for the removal and disposal of the 6" transite water line in the alley?

Answer: Please refer to the Bid Tab, Bid Item number 45. This pay item was revised to read: "REMOVE AND DISPOSE EXISTING 6" TRANSITE WATERLINE, RESTORE SURFACE". All subsequent Bid Item numbers were updated accordingly.

Measurement and payment for this work shall be per linear feet under the bid item, "REMOVE AND DISPOSE EXISTING 6" TRANSITE WATERLINE, RESTORE SURFACE", and shall include all materials and equipment necessary to remove the water main and safely dispose.

Per Addendum #1, the Contractor shall be responsible for maintaining continuous water service to the properties throughout the project. The temporary waterline shall be incidental to the construction of the water main(s). Please refer to Specifications Subsection 601.6 and MAG Specifications Section 601.3.1.