



City of Phoenix
Office of the City Engineer
Design and Construction Procurement
200 W. Washington Street, 5th Floor
Phoenix, Arizona 85003-1611

**PALM LANE STORM DRAIN: 28TH PLACE TO 32ND STREET
DESIGN-BID-BUILD
PROJECT NO. ST83140081-1**

RFX6000001060

ADDENDUM NO. 1

ISSUE DATE: April 7, 2021

Bidders are hereby notified that the Bidding and Contract Documents for the above project, for which Bids are to be received on **Tuesday, April 13, 2021**, are amended as follows:

QUESTIONS AND ANSWERS

Q1.	Will the 2" gas line be relocated prior to commencement of the storm drain?
A1.	South West Gas completed the relocation in May of 2020.
Q2.	Will a designated staging area be provided by the City?
A2.	No
Q3.	Will the residential working hours be the same as Arterial/collector streets(8:30 AM to 4:00 PM)?
A3.	Summer hours are 6:00 am to 2:30 pm / Winter hours are 7:00 am to 3:30 pm
Q4.	Can the residential streets be road closed to thru traffic at the end of each work shift?
A4.	Closures will be determined between the Right-Of-Way inspector and the contractor. It is typical to require the roadways to be opened up at the end of each work shift unless a specific agreement is made with Right-Of-Way.
Q5.	Can residential intersections be closed entirely with applicable detours or half at a time?
A5.	Intersections will not be given full closures. A partial closure would be typical.
Q6.	Will transverse trenches in residential need to be slurry?
A6.	Slurry is an option but not a requirement. Review Section 336.3 of the City of Phoenix Supplement to MAG Specifications.
Q7.	Is the trench detail provided in the geotechnical report the precedent for the entire project?
A7.	No. The details provided in the geotechnical report have locations assigned to them.
Q8.	Will equipment storage requirements be relaxed? (The allowance of only the mainline track hoe to be left on site after each shift)
A8.	No, equipment storage requirements will not be relaxed. Track vehicles can be fenced and barricaded (closed) on the job site. Specifics to be worked out with Construction Inspection Supervisor.

Q9	Will you be accepting quotes for material testing and special inspections, for this project bidding on April 13?
A9	No. We will not be accepting quotes for material testing or inspections.
Q10	We need to confirm quantities for asphalt paving section items 23 and 24. Are you planning to publish paving plans for such?
A10	There are no paving plans for this project. The AC replacement quantities are shown on each sheet where trench paving is to be done. It is shown at the top of the profile in a box under the A or B designation (A & B are backfill type designations, not pavement types).

NOTE: Bidders must acknowledge receipt of this Addendum by listing the number and date, where provided, on the PROPOSAL P.-1

END OF ADDENDUM

Chris Manno
 Civil Engineer III
 Street Transportation Department

